ADDENDUM NO. 1
Issued May 3, 2013

Re-roofing specifications for:
Exposition Building Reroof – Marshfield Fairgrounds Park – Marshfield, WI

Part 1 Section 1.01 Subsection D. – Delete entire section and replaced with the following sentences:

New 60 mil Carlisle Sure-Seal EPDM to be fully adhered to insulation. Membrane to be standard black color. East and west upper and lower edge details shall be a 9" RUSS detail per Carlisle A-1-G. No edges shall be allowed to "buck" water against direction of slope. Existing sheet metal at east and west high wall above lower roof sections shall be removed by the Owner to allow proper installation of membrane up vertical wall to at least the point that the existing roofing materials extend to. Properly flash connection where new roofing materials meet wall materials with a two piece assembly. This shall consist of a termination bar and counter flashing materials that will allow the Owner to remove either the wall's external finish or the roofing materials, without disturbing the opposing materials. This area shall be counter flashed per manufacturers requirements to meet warranty.

Part 1 Section 1.01 Subsection E. – delete the entire wording of this section and replace with the following sentence:

Provide Alternate Price #1 for new 1 inch nominal wood subfascia, metal fascia, and non-vented metal soffit and frieze channel on both east and west upper and lower roof edges.

Part 1 Section 1.02 Subsection F. – delete the entire wording of this section and replace with the following sentence:

The City of Marshfield requires a permit for this work. Contractor is responsible to pay all permit fees. Subcontractors shall also be responsible for permits if needed per City of Marshfield requirements.

Part 1 Section 1.02 Subsection G is created and shall contain the following wording:

A 100% performance and payment bond shall be furnished by the Contractor prior to commencing work.

Part 1 Section 1.02 Subsection H is created and shall contain the following wording.

Asbestos testing of the three roofs indicate that all contain asbestos containing materials (ACM) in the flashing materials only. The layered roofing does not contain any ACM.

Contractor shall be responsible for proper removal and disposals of the old roofing materials as part of their bid.

Part 1 Section 1.05 Subsection C. – second sentence is deleted in its entirety and replaced with the following sentence:

The completion date shall be no later than August 1, 2013.